

Footing Schedule

Mark	Size	Rebar
F-01	24"x24"x10"	None
F-02	30"x30"x10"	(3) #4 or (3) #5 E.W.

- Notes:
- 1) Lap all rebar splices 30" min., U.N.O.
 - 2) Provide 3" min. concrete cover for all rebar, U.N.O.
 - 3) The bottom of all footings to be located 12" min. below grade -OR- below local frost depth, whichever is greater.

